



More than 30 years experience

About Us

 $\sqrt{\text{SINCE 1987}}$

- $\sqrt{10}$ FACTORIES
- $\sqrt{2300} \text{ EMPLOYEES}$
- $\sqrt{\rm YEARLY}~\rm OUTPUT~300000CBM$
- $\sqrt{\rm OSHA\,AS1577\,AS2269\,EN13377\,STANDARDS}$
- $\sqrt{}$ ISO9000, ISO14001, CARB, CE, SONCAP CERTIFIED



VIP Clients



Design Properties

Plank Thickness	1 1/2"
Flexural Stress, Fb	2950 psi
Modulus of Elasticity, E	2.00 × 10 ⁶ psi
Horizontal Shear Stress, Fv	200 psi
Compression Perpendicular to Grain, Fc	435 psi
Coefficient of Variation (MOR)	12%
Raw material	New Zealand radiate pine
Size	T 38/42 * W 225/230 * L 3900-12000MM
Glue	100%WBP glue 72 hours hot water boiling or Melamine Glue 8 hours hot water boiling
Density	560~610KGS/CBM
MC	8-12%
Certificate	CE Standard/SGS
Standard	OSHA Middl <mark>e Dut</mark> y / Heavy Duty AS1577
Other	End Painting, edge chamfered, embossed

General Notes

1. Design properties are determined in accordance with ANSI A10.8-2001, Appendix C.

2. These properties apply only to laminated veneer lumber(LVL) scaffold planks used in conditions where the moisture content of the plank is not expected to exceed 19%. These values apply only to planks used in a flat orientation.

3. Fb,E, and Fv shall be adjusted by a factor of 0.80 when used in conditions where the moisture content of the plank is expected to exceed 19%.

4. No increases in allowable unit stresses are included for load-sharing systems. Values are for new or like-new product.

Specification

Augus Danaitu	045 16 - 10-0
Average Density	615 Kg/m3
Adhesive	Phenolic Formaldehyde Resin
Length Tolerance	-0mm to +3mm
Width Tolerance	-0mm to +1mm
Thickness Telerance	-0mm to +1mm
Product Joins	Butt or scarf joins

Production

It is produced from 3mm thick, rotary peeled softwood veneer layers of Spruce, glued together using a WBP glue to form a continuous 2.5 metre wide billet, with thicknesses ranging from 27 to 75 mm and a maximum length of 24 metres. The billet is then hot pressed and cut to size to make beams, planks, posts or panels or processed into a variety of other products.

Process





Certification

	TEST REPORT No. : SHIN171103618CCM Date : Dec. 05, 2017 Page: 1 of 6
CUSTOMER NAME:	SHANDONG FUSHI WOOD CO., LTD.
ADDRESS:	SOUTH RING ROAD NORTH BOHAI AVENUE TO THE SOUTH, YANGKOU TOWN, SHOUGUANG CITY, SHANDONG, CHINA
Sample Name	: PINE LVL SCAFFOLDING PLANK
Product specification	: 38* <mark>225*400</mark> 0MM
Manufacturer	: Shandong Fushi wood Co., Ltd.
Above information and assumes no responsib information provided by	sample(s) was/were submitted and confirmed by the client. SGS, however bility to verify the accuracy, adequacy and completeness of the sample client.
Test Required	: Please see the next page(s)
Test Method	: OSHA Regulations (Standard-29 CFR)-1926.451
Date of Receipt	: Nov. 28, 2017
Testing Start Date	: Nov. 28, 2017
Testing End Date	: Dec. 05, 2017
Test result(s)	: For further details, please refer to the following page(s) (Unless otherwise stated the results shown in this test report refer only to the sample(s) tested)
Signed for SGS-CSTC Standards T Services (Shanghai) (Joyce Lj	Fechnical Co., Ltd.
Joyce Li Authorized signatory	
「「「「「「」」」	Unless otherwise agreed in writing, this document is issued by the Company subject to its General Conditions of Service printed overleaf, available on request or accessible at http://www.ago.com/en/Terma-and-Condition_aspx.and, for electronic format documents, subject to Terms and Conditions for Electronic Documents at http://www.ago.com/en/Terma-and-Conditions/Terma-Pocument.aspx.



No.69, Block 1159, East Kang Qiao Road, Pudong District, Shanghai, China. 201319 ((86-21)61196300 ((86-21)61191653/68183920 www.sgsgroup.com.cn 中国 - 上海 - 浦东康桥东路1159弄69号 邮编: 201319 ((86-21)61196300 ((86-21)61191653/68183920 e sgs.china@egs.com

	TEST REPO	DRT No. : SHIN17 ⁻ Date : Dec.05 Page: 3 of 6	1103618CCM , 2017
1. Test item: Deflection at 50psf(Test method: OSHA Regulations (Star Test condition: Specimen: 4000mm×225mm×38mm, Test span:1800mm	medium-duty) ndard-29 CFR)-1920 1pc	6.451	
Test result:			
Test item	Test result	Requirement of OSHA	Conclusion
Deflection at 50psf(medium-duty)	8.53mm	≤30.00 mm ^{Note}	Pass
	In test		



Т	EST REPC	DRT No. : SHIN17 [,] Date : Dec.05 Page: 5 of 6	1103618CCM , 2017
 Test item: Supporting at 4×50psf Test method: OSHA Regulations (Standa Test condition: 	(medium-duty) ard-29 CFR)-1926	5.451	
Specimen: 4000mm×225mm×38mm Test span:1800mm	n, 1pc		
Test result:			
Test item	Test result	Requirement of OSHA	Conclusion
Supporting at 4×50psf(medium-duty)	Unbroken	No failure	Pass
Test photo(s):	Intended load ap	oplied or transmitted to it.	
Test photo(s):	In test	pplied or transmitted to it.	

SGS **TEST REPORT** No. : SHIN171103618CCM Date : Dec. 05, 2017 Page: 6 of 6 4. Test item: Supporting at 4×two person-4×500 pounds total Test method: OSHA Regulations (Standard-29 CFR)-1926.451 Test condition: Specimen: 4000mm×225mm×38mm, 1pc Test span:1800mm Test result: Requirement of OSHA Test item Test result Conclusion Supporting at 4×two person-4×500 No failure Unbroken Pass at least 2000lbs Note pounds total Note: OSHA Regulations (Standard-29 CFR)-1926.451(a) (1): Each Scaffold and scaffold component shall be capable of supporting, without failure, its own weight and at least 4 times the maximum intended load applied or transmitted to it. Test photo(s): In test ******** End of report******* In the territory of the People's Republic of China, the test report with CMA logo expresses that the test methods are within the scope of China Metrology Accreditation (CMA); Without CMA logo expresses that part/all of the test methods are not within the scope of China Metrology Accreditation (CMA), and just for client internal reference. www.sy ng District, Shanghai, China. 201319 t (86-21) 61196300 f(86-21)61191853/68183920 ·浦东康桥东路1159弄69号 邮编:201319 t(86-21)61196300 f(86-21)61191853/68183920 e sgs.china@sgs.com 中国

Price List



Contact Us



CEO ceo@fushiwood.com



General Manger boss@fushiwood.com



Sales Director lucyhu@fushiwood.com



Engineer engineer@fushiwood.com



QC Manager fushiqc@fushiwood.com



Logistics Manager fushilogistic@fushiwood.com